



KWS1 - 600/150

KW - Kaltwasser, AG ½ "  
 WW - Warmwasser, AG ½ "  
 E - Entlüftung, IG ½ "  
 Z - Zirkulation, AG ½ "  
 L1,2,3,4 - Befüllen / Entleeren, IG 1½ "  
 L0 - Drainage / Entleeren, AG ¾ "  
 TS1,2,3,4 - Thermosensor / Fühler, IG ½ "  
 TSS1 - Thermosensor / Fühler, IG ½ "

ES - Elektrostab, IG 1½ "  
 TR - Thermoregulator  
 / Manometer, IG ½ "  
 T - Thermometer, IG ½ "  
 VL1 - Solar / Heizung, IG 1 "  
 RL1 - Solar / Heizung, IG 1 "