



KWS2 - 600/150

KW - Kaltwasser, AG 1/2 "
 WW - Warmwasser, AG 1/2 "
 E - Entlüftung, IG 1/2 "
 Z - Zirkulation, AG 1/2 "
 L1,2,3,4 - Befühlen / Entleeren, IG 1 1/2 "
 L0 - Drainage / Entleeren, AG 3/4 "
 TS1,2,3,4 - Thermosensor / Fühler, IG 1/2 "
 TSS1,2 - Thermosensor / Fühler, IG 1/2 "

ES - Elektrostab, IG 1 1/2 "
 TR - Thermoregulator
 / Manometer, IG 1/2 "
 T - Thermometer, IG 1/2 "
 VL1 - Solar / Heizung, IG 1 "
 RL1 - Solar / Heizung, IG 1 "
 VL2 - Solar / Heizung, IG 1 "
 RL2 - Solar / Heizung, IG 1 "